

North Boundary, T. 1 N., R. 35 East.

| | |
|--------|---|
| Chains | links North of Corner to Townships 1 and 2 North, Ranges 34 and 35 East Willamette Meridian. |
| | North 89° 44' East on true line on North boundary of Sec. 6. |
| | Var. 20°00' East. |
| 38.75 | Set post for $\frac{1}{4}$ Sec. corner, from which A Pine 24 ins. in diam. bears S.10°W44 lks. |
| 78.75 | Set post for corner to Secs. 5, 6, 31, 32, from which A Pine 40 ins. in diam. bears N62°W. 41 lks. " " 14 " " " " S80°E.70 lks. |
| | Land, mountainous. Soil, good 2nd rate. Good grass. Pine and fir timber. |
| | North 89° 44' East on true line on North boundary of Sec. 5. |
| | Var. 21° East. |
| 40.00 | Set post for $\frac{1}{4}$ Sec. corner from which A Pine 12 ins. in diam. bears S85°W. 40 lks. |
| 40.75 | Wagon road, corner N & S. |
| 71.00 | Brook, 6 lks. wide, flows S.E. |
| 80.00 | Set post and made stone mound for corner to Secs. 4, 5, 32, 33. |
| | Land, mountainous. Soil, good, 2nd rate. Good grass. Pine timber. May 16, 1871. |
| | North 89°44' East on true line on North boundary of Sec.4. Var. 21° East. |
| 40.00 | Set post and raised stone mound for $\frac{1}{4}$ Sec. corner. |
| 80.00 | Set post and raised stone mound for corner to Secs. 3,4, 33 & 34. |
| | Land, mountainous. Soil, 2d rate. Good grass. |
| | North 89° 44' East on true line on North boundary of Sec.3. |