

North Boundary, Tp. 1, N., R. 35 E.

Chains		
		Var. 20°30' East.
17.10	Brook, 14 lks. wide, flows N.	-140
40.00	Set post and made stone mound for $\frac{1}{4}$ Sec. corner.	+340
80.00	Set post and made stone mound for corner to secs. 2, 3, 34, 35.	-200
	Land, mountainous. Soil, 2nd rate. Good grass. But little timber.	
North 89°44' East on true line on North boundary of Sec.2.		
		Var. 21° 31' East.
18.00	Brook, 6 lks. wide, flows N.W.	-100
40.00	Set basalt stone 14x14x10 for $\frac{1}{4}$ section corner.	+240
80.00	Set post and made stone mound for corner to secs. 1, 2, 35, 36.	
	Land, mountainous.	
	Soil, 2d rate. Good grass.	
North 89° 44' East on true line on North boundary of Sec. 1.		
		Var. 21° East.
40.00	Set basalt stone 18x18x9 for $\frac{1}{4}$ Sec. corner.	
80.00	To corner to Townships 1 & 2 North, Ranges 35 & 36 East Willamette Meridian.	
	Land, mountainous.	
	Soil, 2nd rate. Good grass. Some Pine timber.	
		May 17, 1871.
Field Notes of the Survey of S. bdry. T. 2 N.; R.35, E. Willamette Meridian. By Curran & Noland, under Special Contract, dated May 4, 1889.		
South 89° 48' W. on S. bdry. Sec. 36.		
		Var. 21°15' East.
10.95	Canyon, course N.	-100
19.96	U.R.Bdy. Set a basalt stone 20x10x8 ins., 15 ins. in the ground for closing cor. to Tps. 1 & 2 N.R. 35 E., marked U.R.C.C. on W. face. Raised a mound of stone alongside. Pits impracticable.	