

Chains		
31.00	Top of mountain	+100
40.00	Set a basalt stone 10 x 8 x 7 ins., 7 ins. in the ground for 1/4 Sec. cor. marked 1/4 on N. face. Raised mound of stone alongside. Pits impracticable.	
54.10	Brook. Water in holes. Course N.E.	-100
63.60	Top of ridge. Course N.	+400
78.50	Canyon Creek. Water in holes. Course N.	-1200
80.00	Set a basalt stone 12 x 9 x 7 ins., 8 ins. in the ground for cor. to secs. 3, 4, 33 & 34. Marked 3 notches on E. & W. edges. Raised mound of stone alongside. Pits impracticable.	
	Land, very mountainous 80. chs.	
	Soil, rocky, 4th rate.	
	Scattering pine timber in canyon as noted.	
	South 89°48' W. on S. bdy. S. 33.	
	Var. 23°20' E.	
18.60	Pine tree 16 ins. in diam. on top of hill.	+200
30.80	Gulch.	-100
33.50	Top of hill.	+200
40.00	Set a basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/4 Sec. cor., marked 1/4 on N. face. Raised stone mound alongside. Pits impracticable.	
43.50	Canyon. Course N.E.	-200
63.50	Summit of ridge.	+400
78.60	Canyon, Course N.E.	-200
80.00	Set a post 48 x 4 x 4 ins., 2 ft. in the ground for cor. to Secs. 4, 5, 32 & 33. Marked T.2 N.S.32 on N.W., R.35E. S.33 on N.E., T.1 N.R. 35 E. S.4 on S.E., S.5 on S.W. faces with 4 notches on East and 2 notches on W. edges. Raised a mound of stone alongside. Pits impracticable.	
	Land, mountainous. 80.00 chs.	
	Scattering timber in canyons.	
	Soil, 4th rate.	