

T. 1 N., R. 35 E.

Chains		
	South 89°48' W. on So. bdry Sec. 32. Var. 20° East.	
6.50	Top of ridge sloping S.	
14.60	Canyon and branch. Course S.E.	-400
38.50	Ascend.	
40.00	A pine 30 ins. in diam., which I marked $\frac{1}{4}$ S. on N. face for $\frac{1}{4}$ Sec. cor. No trees within limits. Raised mound of stone alongside. Pits impracticable.	
80.00	Set post 48x4x4 ins. 2 ft. in the ground for cor. to secs. 5,6,31 & 32, marked T.2,N.S31 on N.W., R.35 E.S.32 on N.E., T.1 N.R.34 E.S6 on S.W., S.5 on S.E. faces with 5 notches on E. & 1 Notch on W. edges, from which A Pine 12 ins. in diam. bears N.80°E. dist. 85 lks., marked T.2 N. S.32, B.T. A Pine 7 ins. in diam. bears S.55° W.dist.51 lks., marked T.1 N.S. 6 B.T. A Pine 24 ins. in diam. bears N.70° W. dist. 99 lks., marked R35E.S31,B.T. A Pine 16 ins. in diam. bears S.30°E. dist. 50 lks., marked S5.B.T.	
	Land, rolling.	
	Soil, 2nd rate.	
	Scattering pine timber. Good bunch grass.	
	S. 89° 48' W. on S. bdy. Sec. 31. Var.22°30' East.	
10.50	Top of hill	+100
16.10	Gulch, course N.	-100
40.00	Set a post 36 x 3 x 3 ins. 2 ft. in the ground for $\frac{1}{4}$ Sec. cor.; marked $\frac{1}{4}$ S. on N. face, from which A Fir 16 ins. in diam. bears N45°E.dist. 20 lks., marked $\frac{1}{4}$ S.B.T. A Fir 18 ins. in diam. bears S.10°E. dist. 12 lks., marked $\frac{1}{4}$ S.B.T.	
75.90	To cor. to Tps. 1 & 2 N.Rs. 34 & 35 E.	
	Land, rolling. Good pine grass.	
	Soil, 2nd rate. Good pine and hemlock timber. June 16, 1887.	