

Base Line, T. 1 N.R. 35 E. (So. boundary)

	<p>marked S.C. $\frac{1}{4}$ S.B.T.</p> <p>The other old B.T. has been cut down.</p>	
40.60	Old Emigrant wagon road, course N.W.	
68.00	Descend.	
76.00	O.R. and N. Railroad, course N30W.	
79.50	Meacham creek, 25 lks. wide, course N.	
80.00	<p>Set basalt stone 20 x 10 x 8 ins., 15 ins. in the ground on E. bank of creek at exact place of old cor. post for cor. to secs. 34 and 35, marked S.C. with 2 notches on E. edge and 4 notches on W. edge, and raised mound of stone 2 ft. high, $4\frac{1}{2}$ ft. base over it, from which</p> <p>A Spruce 12 ins. diam. (old Witness tree) bears N5°E. 43 lks. dist., marked S.C.T.1 N.R. 35E.S35 B.T.</p> <p>The other old Bearing trees have fallen.</p> <p>Land, rolling.</p> <p>Soil, 3rd rate.</p> <p>Heavy timber, consisting of Black & Yellow Pine, Spruce and Fir. 80. chs.</p> <p>Good grazing land.</p>	
	<p>East on S. bdy. sec. 35, retracing line of old survey.</p> <p style="text-align: right;">Var. $18\frac{1}{2}^{\circ}$ East.</p>	
20.00	Top of hill.	†500
30.75	Canon, course N.	-200
35.00	Top of hill.	†150
40.00	<p>Set post 3 ft. long, 3 ins. square, 24 ins. in the ground in exact place of old cor. for $\frac{1}{4}$ sec. cor., marked S.C. $\frac{1}{4}$ S. on N. face, from which</p> <p>A Spruce, 8 ins. in diam. bears N.10°E.40 lks. dist., marked S.C. $\frac{1}{4}$ S.B.T.</p> <p>A Spruce, 8 ins. in diam. bears S.40°E. 20 lks. dist., marked S.C. $\frac{1}{4}$S B.T.</p> <p>These are the original bearing trees.</p> <p>Descend.</p>	
46.00	Touch Meacham Creek.	