

## Subdivisional Lines, T. 1 N., R. 35 East

Chains		
	N. face. Raised mound of stone over it. Pits impracticable.	
40.00	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ S. cor., marked $\frac{1}{4}$ on W. face, from which A Pine 24 ins. diam. bears N88°E.61 lks.dist., marked $\frac{1}{4}$ S.B.T.. A Pine 20 ins. diam. bears S55°W43 lks.dist., marked $\frac{1}{4}$ S.B.T.	
80.00	Set basalt stone 20 x 8 x 7 ins., 16 ins. in the ground for cor. to secs. 22, 23, 26 & 27, marked with 2 notches on S and E edges, from which A Pine 30 ins. diam. bears S.40°E.100 lks.dist., marked T1 N R 35 E S26 B.T. No other trees in limits. Raised mound of stone over it. Pits impracticable. Land, rolling. Heavily timbered with Pine, Fir & Spruce 55.25 chs. Underbrush: Willow, Fir & Spruce. Soil, poor & rocky. Grass poor.	
East on true line bet. secs. 23 & 26.		
Var. 20° East.		
5.00	Canon N.E.	-100
8.50	Top ridge N.E.	+100
15.00	Canon and Spring Branch 2 lks.N.E.	-200
20.00	Intersect U.R. bdy. 112 lks. S 20° W of 48th mile cor. and set post 4 ft. long, 4 ins. square, 24 ins. in the ground for Closing corner to secs. 23 & 26, marked U.R.C.C on W. T1N S23 on N.; R35E.S26 on S faces, from which A fir 18 ins. diam.bears S85°E 23 lks. dist., marked T1N S26 U.R.C.C.B.T. A fir 12 ins.diam.bears N55°W 10 lks. dist.,marked S23 U.R.C.C.B.T. Land, mountainous 20 chs.. Soil, 2nd rate. Timber: Pine and fir. Grass,poor.	