

Subdivisional lines, T. 1 N., R. 35 E.

Chains		
	East on random bet. S 9 & 16.	
		Var. 20-3/4° East.
40.00	Set temporary 1/4 S. cor. and at	
80.10	Intersect E. bdy. 23 lks. S of cor. to Secs. 9, 10, 15 & 16,	
	Thence	
	S.89° 50' W. on true line.	Var. 17 1/4° East.
7.50	Creek N.	-200
35.00	Summit ridge N.E.	+800
38.50	Gulch N.E.	-150
40.05	Set basalt stone 12x12x6 ins., 8 ins. in the ground for 1/4 S. cor., marked 1/4 on N. face, from which A fir 8 ins. in diam. bears N.40°E.37 lks. dist., marked 1/4 S.B.T. A fir 8 ins. in diam. bears S45°E. 23 lks. dist., marked 1/4 S.B.T.	
55.50	Summit ridge N.	+300
60.00	Gulch N.	-100
65.00	Summit ridge N.	+100
68.90	Wagon road N.	-50
74.75	Wagon road N.W.	+100
80.10	Cor. to secs. 8, 9, 16 & 17. Land, rough and mountainous 80.10 chs. Timber: Pine, fir and tamarack, scattering. Grass, good. Soil, 2nd rate and rocky.	
North bet. secs. 8 & 9.		
		Var. 19°30' East.
40.00	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/4 S. cor., marked 1/4 S on W face, from which A Pine 30 ins. in diam. bears N.60°E.132 lks. dist., marked 1/4 S.B.T. A Pine 4 ins. in diam. bears West 3 lks. dist., marked 1/4 S.B.T.	
46.00	Wagon road N.W.	