

Subdivisional lines, T. 1 N., R. 35 E.

Chains	
	East on random bet. secs. 20 & 29. Var. $20\frac{1}{2}^{\circ}$ East.
40.00	Set temporary $\frac{1}{4}$ S. cor. and at
80.30	Intersect E. bdy. at corner to secs. 20, 21, 28 & 29, Thence West on true line. Var. 19° East.
30.00	Old stage road N.
40.15	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ S. cor., marked $\frac{1}{4}$ S on N. face, from which A fir 36 ins. in diam. bears $N.45^{\circ}W.$ 29 lks. dist., marked $\frac{1}{4}$ S. B. T. A pine 12 ins. in diam. bears $S.69^{\circ}E.$ 30 lks. dist., marked $\frac{1}{4}$ S. B. T.
61.10	Head of draw W.
80.30	Cor. to secs. 19, 20, 29 & 30. Land, mostly level and high. Timber, pine and fir and underbrush. Soil, 1st rate.
	West on random bet. secs. 19 & 30. Var. $20\frac{1}{2}^{\circ}$ East.
40.00	Set temporary $\frac{1}{4}$ S. cor. and at
79.65	Intersect Tp. line 23 lks. N of corner to secs. 19, 30, 24 & 25. Thence N. $89^{\circ} 50'$ E. on true line. Var. $20\frac{1}{2}^{\circ}$ East.
37.00	Enter heavy timber.
39.65	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ S on N. face, from which A tamarack 12 ins. diam. bears $N.60^{\circ} W.$ 13 lks. dist., marked $\frac{1}{4}$ S. B. T. A fir 12 ins. in diam. bears $S.65^{\circ} E.$, 27 lks. dist., marked $\frac{1}{4}$ S. B. T.
46.65	Leave timber.
79.65	Cor. to secs. 19, 20, 29 & 30. Land, rolling. Soil, 1st & 2nd rate. Timber, heavy pine, fir and tamarack 9.65 chains.