

Subdivisional lines, T. 1 N., R. 35 E.

Chains		
	A pine 12 ins. in diam. bears N.80°E. 24 lks. dist., marked $\frac{1}{4}$ S. B. T.	
	A pine 14 ins. in diam. bears S.45° E.37 lks. dist., marked $\frac{1}{4}$ S. B. T.	
57.78	Creek, 8 lks. runs N.E.	-25
76.30	Creek, 10 lks., runs S.E.	-50
80.30	Cor. to secs. 17, 18, 19 & 20. Land, rolling. Soil, 3rd rate. Timber, pine and fir, scattering.	
	June 26, 1887.	
	<hr/>	
	West on random bet. secs. 18 & 19. Var. 19° East.	
40.00	Set temporary $\frac{1}{4}$ S. cor. and at	
79.75	Intersect Tp. line 14 lks. N of cor. to secs. 13, 24, 18 & 19, Thence N.89°54' E. on true line. Var. 18° East.	
39.75	A pine 16 ins. diam. marked $\frac{1}{2}$ S on N. face for $\frac{1}{4}$ Sec. cor., from which A pine 12 ins. diam. bears N.20°W.60 lks. dist.,marked $\frac{1}{4}$ S. B. T. A pine 10 ins. in diam. bears S.55°W.25 lks. dist., marked $\frac{1}{4}$ S. B. T.	
	Descend gradual slope.	
54.00	Canon	-250
	Ascend	
64.00	Top of rolling hill.	+200
	Descend.	
70.00	Small ravine.	-20
79.75	Cor. to secs. 17, 18, 19 & 20. Land, gently rolling. Soil, 1st $\frac{1}{2}$ mile, good; last $\frac{1}{2}$, 2nd rate. Timber, scattering pine and fir. Bunch grass, good.	
	<hr/>	