

## Subdivisional Lines, T. 1 N., R. 35 E.

Chains	Descend.	
54.00	Gulch, S.W.	-20
67.00	Summit divide.	+100
70.00	Enter timber, scattering pine.	
79.90	Cor. to secs. 7, 8, 17 and 18.	
	Land, mostly rolling.	
	Soil, generally 1st rate.	
	Timber, scattering pine and fir. Some underbrush.	
	Bunch grass, fine.	
	<hr/>	
	West on random bet. secs. 7 and 18.	
	Var. $19\frac{1}{2}^{\circ}$ East.	
40.00	Set $\frac{1}{4}$ sec. cor. temporary and at	
80.00	Intersect Tp. line 23 lks. N. of corner to secs. 12, 13, 17 and 18.	
	Thence	
	N. $89^{\circ} 50'$ E. on true line.	
	Var. $19^{\circ}$ East.	
	Descend.	
22.50	Canyon N. W.	-600
35.00	Ascend. Top of ridge S.	+500
38.00	Begin descent.	
40.00	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ S. on N. face, from which A fir 14 ins. in diam. bears N. $70^{\circ}$ E. 17 lks. dist., marked $\frac{1}{4}$ S. B. T. A fir, 16 ins. in diam. bears S. $45^{\circ}$ E. 28 lks. dist., marked $\frac{1}{4}$ S. B. T.	
	Descend abruptly.	
54.75	N. fork McKay's Creek, 5 lks., runs S.W. in canyon. Ascend steep hill side.	-600
79.00	Top of hill.	+600
80.00	Cor, to secs. 7, 8, 17 and 18. Land, rough and mountainous, 80.00 chs.	