

Subdivisional lines, T. 1 N., R. 35 E.

Chains		
40.12	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ Sec. cor., marked $\frac{1}{4}$ S on N. face, from which A pine 24 ins. in diam. bears N.32° W. 30 lks. dist., marked $\frac{1}{4}$ S. B. T. A pine 20 ins. in diam. bears S.65°W.71 lks. dist., marked $\frac{1}{4}$ S. B. T.	
60.00	Canon, S.W.	-150
65.50	Top hill or ridge S.	+200
79.50	Gulch and dry bed of creek. Ascend.	- 50
80.12	Cor. to secs. 5, 6, 7 and 8. Land, badly broken. Soil, 2nd rate, rocky. Timber, pine and fir scattering. Some brush. Bunch grass, fine.	
North bet. secs. 5 and 6.		
	Var. 19° 20' East	
	Ascend gradual slope..	
37.50	Pendleton and La Grande wagon road N.W. and S.E.	
38.00	Spring called Parker's Well and nearly dry.	
40.00	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ Sec. cor., marked $\frac{1}{4}$ S on N. face, from which A pine 12 ins. in diam. bears N.50° E., 41 lks. dist., marked $\frac{1}{4}$ S. B. T. A pine 18 ins. in diam. bears S.45° E., 92 lks. dist., marked $\frac{1}{4}$ S. B. T.	
63.00	Trail N.E.	
64.00	Enter scattering pine timber.	
80.12	Intersect Tp. line 400 lks. East of cor. to secs. 31 & 32, T 2 N R 35 E and set post 4 ft. long, 4 ins. square, 24 ins. in the ground for closing cor. to secs. 5 & 6, marked C.C.T1 N R 35 E. on S.; S5 on E and S6 on W. faces with 5 notches on E and 1 notch on W. edges, from which A pine 30 ins. in diam. bears S45°E.94 lks. dist., marked TI N S5 B T.	