

Subdivisional lines, T. 1 N., R. 35 E.

Chains

A pine 40 ins. in diam. bears S.30 W.28 lks. dist.,
marked R35 E S6 B.T.

A pine 36 ins. in diam. bears N 16 W 70 lks. dist.,
marked T2 N R 35 E. B. T.

Land, nearly level.

Soil, 1st rate on last $\frac{1}{2}$ mile.

Timber, pine, scattering. Bunch grass, good.

June 28, 1887.

General Description.

This township is rough and mountainous, cut with deep and
rocky canons. There is good pine, fir and tamarack
timber and good bunch grass.

Soil rocky, 3rd rate.

Field Notes of the survey of the Subdivision Lines of
T. 1 N. R. 35 E., as surveyed by Manius Buchanan,
under his contract No. 635, dated April 19th, 1895.

Post for cor. to secs. 35 and 36 is gone; the witness trees
are all standing and agree with the notes furnished me by
the Surveyor General which to perpetuate, I set a tamarac
post 3 ft. long, 4 ins. square, 24 ins. in the ground for
standard cor. to secs. 35 and 36, marked S.C. T.1 N.R.35
E. on N.; S.36 on E. and S..35 on W., with 1 notch on E.
and 5 on W. faces.

Thence, I run

N.0° 01' W. bet. secs. 35 and 36.

Var. 18°36' East.

Descend gradual-through timber.

7.50 Descend steep N. slope, 300 ft.

17.00 O.R.& N. R.R. course E. and W.

23.00 Meacham Creek 33 lks. wide, course East.

Ascend W. face - rocky.

40.00 On steep W. hillside, set a basalt stone 20 x 10 x 10 ins.
15 ins. in the ground for $\frac{1}{2}$ Sec. cor., marked $\frac{1}{2}$ S. on W.
face, from which