

Subdivisions, T. 1, N., R. 35 E.

Chains

(For description of this line, "W. bet. secs. 27 & 34", see page 67, Corrections of Subdivisions.)

Land, nearly level. Soil, sandy loam, 3rd rate.

Timber, heavily timbered with pine, fir and tamarac.

Heavily timbered and mountainous lands 7.70 chs.

(See note 2nd on page 65.)

No. 0°02' W. on a random line bet. secs. 26 and 27.

Ascend gradually through heavy timber.

0.40 (For correction of this line, see page 66, Correction of Subdivisions).

24.42 Intersect U.I.R. line 20 lks. S. 20° W. of closing corner to secs. 26 and 27, which is a mound of stone without marks or witnesses as I can find.

To verify this cor., I continue line

No. 0°02' W.

40.34 The $\frac{1}{4}$ sec. cor., which is a stone 3 x 8 x 7 ins. above ground, marked and witnessed as described by the Surveyor General, bears E. 15 lks.

Thence, I run

S. 0° 11' W. on true line bet. secs. 26 and 27.

Descend gradual, no timber.

15.90 Intersect U.I.R. line: At point of intersection, Set a tamarack post 3 ft. long, 4 ins. square, 24 ins. in the ground for closing corner to secs. 26 and 27, marked C.C.T.1 N.R.35 E. on W.; S.27 on S.W., and S.26 on E. faces. (For corrections of this corner, see page 66, Correction of Subdivisions).

17.00 Enter heavy timber, course S.E. and N.W.

40.34 The cor. to secs. 26, 27, 34 and 35.

Land, hilly.

Soil, sandy loam, 3rd rate.

Timber: Heavily timbered with pine, fir and tamarac.

Mountainous and heavily timbered lands 40.34 chs.

June 22nd, 1895.