

Subdivisions, T. 1 N., R. 35 E.

Chains	<p>S.89°42' W. on true line bet. secs. 13 and 24. Descend open W. hillside.</p> <p>17.00 Enter heavy timber and undergrowth-bears N & S.</p> <p>19.13 Creek, now dry, course N.W. Ascend.</p> <p>24.00 Leave timber, bears N.W. and S.E.</p> <p>26.00 Summit of N.W. point; descend steep.</p> <p>27.20 Enter timber, bears N.W. and S.E.</p> <p>29.70 Creek channel, now dry, 10 lks. wide - course N.W.; ascend steep.</p> <p>34.00 Leave timber; bears N.W. and S.E.</p> <p>36.00 Summit of hill bears N.W. and S.E. Descend steep. Enter timber</p> <p>39.95½ Set a fir post 3 ft. long, 3 ins. square, 24 ins. in the ground for ¼ sec. cor., marked ¼ S. on N. face, from which</p> <p style="padding-left: 40px;">A fir 9 ins. in diam. bears N.84°W. 24 lks. dist., marked ¼ S. B. T., and</p> <p style="padding-left: 40px;">A fir 9 ins. in diam. bears S.65½° E. 75 lks. dist., marked ¼ S. B. T.</p> <p>53.51 Creek, 10 lks. wide; course N.; ascend steep E. face - leave timber.</p> <p>62.45 Summit of ridge 600 ft. above creek; bears N and S.</p> <p>76.50 Enter timber.</p> <p>79.91 The cor. to secs. 13, 14, 23 and 24.</p> <p>Land, mountainous. Soil, sandy loam, 2nd to 4th rate. Timber: Pine, fir, tamarac and spruce. Undergrowth of pine, tamarac, fir, willow and chapparal.</p> <p>Mountainous, 79.91 chs; heavily timbered and with dense undergrowth 34.81 chs.</p>
33.70	<p>N.89° 42' W. on a random line bet. secs. 14 and 23.</p> <p>Intersect U. I. R. line at closing corner to secs. 14 and 23, which is a post in mound of stone; the post being decayed, I set a new post and mark similar to old one-to-wit: set a fir post 3 ft. long, 4 ins. square, 24 ins. in the ground for closing corner to secs. 14 and 23; marked U.R.C.C. on W.; T.1 N.S.14 on N., and</p>