

Subdivisions of T. 1 N., R. 36 E.

Chains	<p>and raised a mound of stone alongside.</p> <p>Land, mountainous.</p> <p>Soil, sandy loam and stony, 2nd and 3rd rate.</p> <p>Timber, scattering pine.</p> <p style="text-align: right;">September 14, 1882.</p>
<p>40.00</p> <p>80.22</p> <p>40.11</p> <p>80.22</p>	<p>East on a random line between secs. 23 and 26.</p> <p style="text-align: right;">Var. 21°E.</p> <p>Ascend.</p> <p>Set temporary $\frac{1}{4}$ sec. cor.</p> <p>Intersect 26 lks. N. of the cor. to secs. 23, 24, 25 and 26.</p> <p>Thence I run</p> <p>N. 89°49'W. on a true line between secs. 23 and 26.</p> <p>Set a basalt stone, 12x10x8 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone alongside.</p> <p>The cor. to secs. 22, 23, 26 and 27.</p> <p>Land, mountainous.</p> <p>Soil, sandy loam, 2nd rate.</p> <p>Timber, scattering pine with dense undergrowth of wild cherry and mountain laurel.</p>
<p>17.00</p> <p>35.00</p> <p>40.00</p> <p>47.00</p> <p>80.00</p>	<p>North between secs. 22 and 23.</p> <p style="text-align: right;">Var. 21°E.</p> <p>Ascend about 200 ft. to</p> <p>Top of ridge, course S.W.</p> <p>Bottom of gulch about 200 ft. below ridge, course S.W.</p> <p>Set a basalt stone, 15x10x4 ins., 10 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, and raised a mound of stone alongside.</p> <p>Top of ridge about 300 ft. above gulch, course S.W.</p> <p>Descend about 300 ft. to</p> <p>Set a basalt stone, 14x10x8 ins., 9 ins. in the ground, for cor. to secs. 14, 15, 22 and 23, and raised a mound of stone alongside.</p>