

Subdivisions of T. 1 N., R. 36 E.

Chains	
	<p>notches on S. and E. edges, from which,</p> <p>A pine, 22 ins. diam., bears N.15°E., 31 lks. dist., marked T 1 N R 36 E S 15 B T.</p> <p>A fir, 18 ins. diam., bears S.25°E., 85 lks. dist., marked T 1 N R 36 E S 22 B T.</p> <p>A fir, 28 ins. diam., bears S. 35°W., 87 lks. dist., marked T 1 N R 36 E S 21 B T.</p> <p>A pine, 40 ins. diam., bears N.80°W., 48 lks. dist., marked T 1 N R 36 E S 16 B T.</p> <p>Land, on S. 45.00 chs. level, remainder mountainous. Soil, sandy loam, 2nd rate. Heavily timbered with pine and fir.</p>
	<p>East on a random line between secs. 15 and 22. Var. 18½°E.</p> <p>Ascend hill.</p> <p>39.00 Top of ridge about 500 ft. above sec. cor., course S.W.</p> <p>40.00 Set temporary ¼ sec. cor.</p> <p>77.50 Bottom of gulch about 300 ft. below ridge, course S.W.</p> <p>80.56 Intersect 33 lks. S. of the cor. to secs. 14, 15, 22 and 23.</p> <p>Thence I run S.89°46'W. on true line between secs. 15 and 22.</p> <p>40.28 Set a basalt stone, 13x9x8 ins., 9 ins. in the ground, for ¼ sec. cor. marked ¼ on N. face, and raised a mound of stone alongside.</p> <p>80.56 The cor. to secs. 15, 16, 21 and 22. Land, mountainous. Soil, sandy loam and stony, 2nd and 3rd rate. Timber, scattering fir and pine.</p>
	<p>North between secs. 15 and 16. Var. 18½°E.</p> <p>Ascend about 250 ft. to</p> <p>29.00 Top of ridge, course W.</p> <p>39.00 Bottom of gulch about 150 ft. below ridge, course W.</p>