

Subdivisions of T. 1 N., R. 36 E.

Chains	<p>Land, mountainous.</p> <p>Soil, sandy loam and stony, 2nd and 3rd rate.</p> <p>Timber, scattering fir and pine.</p> <p style="text-align: right;">September 17, 1882.</p>
	<p>North between secs. 9 and 10.</p> <p style="text-align: right;">Var. 22 3/4°E.</p> <p>Descend about 25 ft. to</p> <p>1.50 Dry bed of creek, course W.</p> <p>22.50 Top of ridge about 250 ft. above creek bed, course W.</p> <p>Descend about 250 ft. to</p> <p>34.50 Bottom of gulch, course W.</p> <p>40.00 Set a basalt stone, 14x12x5 ins., 9 ins. in the ground, for 1/4 sec. cor. marked 1/4 on W. face, and raised a mound of stone alongside.</p> <p>50.00 Top of ridge about 200 ft. above gulch, course W.</p> <p>60.00 Bottom of gulch about 100 ft. below ridge, course W.</p> <p>68.50 Top of ridge about 100 ft. above gulch, course W.</p> <p>80.00 Set a basalt stone, 15x8x8 ins., 10 ins. in the ground, for cor. to secs. 3, 4, 9 and 10, marked with 5 notches on S. and 3 notches on E. edges, from which,</p> <p style="padding-left: 40px;">A pine, 12 ins. diam., bears S.60°W., 82 lks. dist., marked T 1 N R 36 E S 9 B T.</p> <p style="padding-left: 40px;">A pine, 14 ins. diam., bears N.70°W., 47 lks. dist., marked T 1 N R 36 E S 4 B T.</p> <p style="padding-left: 40px;">No other tree within limits, and raised a mound of stone alongside.</p>
	<p>Land, mountainous.</p> <p>Soil, sandy loam, 2nd rate.</p> <p>Timber, scattering fir and pine.</p>
	<p>East on a random line between secs. 3 and 10.</p> <p style="text-align: right;">Var. 23 1/4°E.</p> <p>Ascend.</p> <p>40.00 Set temporary 1/4 sec. cor.</p> <p>67.00 Top of ridge about 600 ft. above last sec. cor., course N.W.</p>