

## Subdivisions of T. 1 N., R. 36 E.

Chains	<p>A fir, 8 ins. diam., bears N.70°E., 6 lks. dist., marked <math>\frac{1}{4}</math> S B T.</p> <p>A fir, 12 ins. diam., bears N.60°W., 9 lks. dist., marked <math>\frac{1}{4}</math> S B T.</p> <p>78.50 Meacham creek, 50 lks. wide, course S.E.</p> <p>79.75 Wagon road, course N.W.</p> <p>80.00 Set a post 4 ft. long, 4 ins. square, 24 ins. in the ground, for cor. to secs. 29, 30, 31 and 32 marked T 1 N S 29 on N.E., R 36 E S 32 on S.E., S 31 on S.W., and S 30 on N.W. faces with 1 notch on S. and 5 notches on N. edges, from which,</p> <p>A fir, 24 ins. diam., bears N.30°E., 46 lks. dist., marked T 1 N R 36 E S 29 B T.</p> <p>A fir, 36 ins. diam., bears S.20°E., 12 lks. dist., marked T 1 N R 36 E S 32 B T.</p> <p>A fir, 10 ins. diam., bears N.60°W., 100 lks. dist., marked T 1 N R 36 E S 30 B T.</p> <p>No other tree within limits.</p> <p>and raised a mound of stone alongside.</p> <p>Land, mountainous.</p> <p>Soil, 2nd rate.</p> <p>Heavily timbered with fir, tamarack and pine.</p> <p style="text-align: right;">September 20, 1882.</p>
	<p>East on a random line between secs. 29 and 32.</p> <p style="text-align: center;">Var. <math>22\frac{1}{2}</math>°E.</p> <p>Ascend about 200 ft. to</p> <p>30.00 Top of ridge, course S.W.</p> <p>40.00 Set temporary <math>\frac{1}{4}</math> sec. cor.</p> <p>42.00 Bottom of gulch about 150 ft. below ridge, course S.W.</p> <p>Ascend about 400 ft. to</p> <p>80.32 Intersect 25 lks. N. of the cor. to secs. 28, 29, 32 and 33.</p> <p>Thence I run</p> <p>N.89°49'W. on a true line between secs. 29 and 32.</p>