

Subdivisions of T. 1 N., R. 36 E.

Chains	<p>East on a random line between secs. 17 and 20.</p> <p>Var. $19\frac{1}{2}^{\circ}$E.</p> <p>Descend.</p> <p>40.00 Set temporary $\frac{1}{4}$ sec. cor.</p> <p>44.00 Bottom of gulch about 250 ft. below sec. cor., course N.</p> <p>53.25 Top of ridge about 100 ft. above gulch, course N.</p> <p>67.50 Bottom of gulch about 100 ft. below ridge, course N.W.</p> <p>80.44 Intersect 18 lks. N. of the cor. to secs. 16, 17, 20 and 21.</p> <p>Thence I run</p> <p>N. $89^{\circ}52'$W. on a true line between secs. 17 and 20.</p> <p>40.22 Set a basalt stone, 16x14x3 ins., 11 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, from which,</p> <p>A pine, 28 ins. diam., bears N. 70°E., 191 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>A pine, 16 ins. diam., bears S. 35°E., 214 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>80.44 The cor. to secs. 17, 18, 19 and 20.</p> <p>Soil, sandy loam, 2nd rate. Land, mountainous.</p> <p>Timber, scattering fir, pine and tamarack, with dense undergrowth of buck brush and wild cherry.</p>
	<p>West on a random line between secs. 18 and 19.</p> <p>Var. $19\frac{1}{2}^{\circ}$E.</p> <p>40.00 Set temporary $\frac{1}{4}$ sec. cor.</p> <p>44.50 Dry bed of creek, course S.E.</p> <p>90.32 Intersect W. boundary, 75 lks. S. of the cor. to secs. 18, 19, 13 and 24, which is a post 4 ins. square marked T 1 N S 18 on N.E., R 36 E S 19 on S.E., R 35 E S 24 on S.W., and S 13 on N.W. faces with 3 notches on N. and S. edges, and a mound of stone around post.</p> <p>Thence I run</p> <p>S. $89^{\circ}28'$E. on a true line between secs. 18 and 19.</p> <p>50.32 Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S on N. face, from which,</p>