

West Boundary of T. 1 N., R. 37 E.

Chains	<p>19 on N.E., R 37 E S 30 on S.E., R 36 E S 25 on S.W., and S 24 on the N.W. angles of X.</p> <p>A fir, 18 ins. diam., bears S.28°W., 78 lks. dist., marked T 1 N R 36 E S 25 B T.</p> <p>Land, rough broken and mountainous.</p> <p>Soil, rocky, 4th rate.</p> <p>Timber, pine and fir.</p> <p style="text-align: right;">Sept. 14, 1881.</p>
	<p>N. between secs. 19 and 24.</p> <p style="text-align: center;">Var. 21° E.</p>
10.00	<p>Cross a canyon, course S.E., and ascend over very rocky ground with dense undergrowth.</p>
40.00	<p>Set post $3\frac{1}{2}$ ft. long, 3 ins. square, 18 ins. in the ground on S. side of steep hill, 100 ft. above bottom of ravine in open pine timber for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S on E. and W. faces.</p> <p>A pine, 30 ins. diam., bears S.6°W., 250 lks. dist., marked $\frac{1}{4}$ S B T.</p>
	<p>Ascend a point of mountain.</p>
64.42	<p>Summit of peak 2000 ft. above Meacham creek.</p>
80.00	<p>Set post $4\frac{1}{2}$ ft. long, 4 ins. square, 2 ft. in the ground with a mound of stone around 3 ft. at base, 18 ins. high, for cor. to secs. 13, 18, 19 and 24 marked T 1 N S 18 on N.E., R 37 E S 19 on S.E., R 36 E S 24 on S.W., and S 13 on the N.W. faces with 3 notches on the N. and S. edges.</p> <p>A pine, 24 ins. diam., bears N.50°E., 119 lks. dist., marked T 1 N R 37 E S 18 B T.</p> <p>A fir, 24 ins. diam., bears N.61°W., 80 lks. dist., marked T 1 N R 36 E S 24 B T.</p> <p>A pine, 16 ins. diam., bears S.67°W., 62 lks. dist., marked T 1 N R 36 E S 24 B T.</p>
	<p>Land, rough, broken and mountainous.</p> <p>Soil, rocky and nearly barren, 4th rate.</p> <p>Timber, scattering pine and fir.</p>