

West Boundary of T. 1 N., R. 37 E.

Chains	<p>N. between secs. 13 and 18.</p> <p style="text-align: center;">Var. 23°E.</p> <p>Descend through heavy timber and dense undergrowth.</p> <p>39.00 Cross ravine, course S.20°E., and ascend.</p> <p>40.00 Set post 3½ ft. long, 3 ins. square, 18 ins. in the ground, on the E. side of canyon, 25 ft. above the bottom, for ¼ sec. cor. marked ¼ S on E. and W. faces.</p> <p style="padding-left: 40px;">A fir, 10 ins. diam., bears N.33°W., 20 lks. dist., marked ¼ S B T.</p> <p style="padding-left: 40px;">A fir, 4 ins. diam., bears S.60°E., 10 lks. dist., marked ¼ S B T.</p> <p>Ascend.</p> <p>On West side of canyon.</p> <p>80.00 A stone, 24x30, in mountain side facing W., 50 ft. above bottom of ravine which I marked with an X on W. face for cor. to secs. 7, 12, 13 and 18 marked T 1 N S 7 on N.E., R 37 E S 18 on S.E., R 36 E S 13 on S.W., and S 12 on the N.W. angles of X with 4 notches on the S. and 2 notches on N. edges.</p> <p style="padding-left: 40px;">A pine, 24 ins. diam., bears S.2°W., 200 lks. dist., marked T 1 N R 36 E S 13 B T.</p> <p>Land, broken and mountainous.</p> <p>Soil, rocky, 4th rate.</p> <p>Timber, pine.</p> <p style="text-align: right;">Sept. 15, 1881.</p>
	<p>N. between secs. 7 and 12.</p> <p style="text-align: center;">Var. 23°E.</p> <p>Ascend through dense undergrowth, buck brush.</p> <p>10.00 A glade on bench of mountain.</p> <p>40.00 Set post 3½ ft. long, 3 ins. square, 12 ins. in the ground, with mound of stone around 3 ft. at the base, 18 ins. high on a bald gravelly point facing N. for ¼ sec. cor. marked ¼ S on the E. and W. faces.</p> <p style="padding-left: 40px;">A pine, 3 ins. diam., bears N.19°W., 86 lks. dist., marked ¼ S B T.</p>