

West Boundary of T. 1 N., R. 37 E.

Chains	
	<p style="text-align: right;">Var. 22°15'E.</p> <p>A noon latitude, 45°36'N.</p>
41.00	<p>Enter swamp and cross the head of branch, course E.</p> <p>Dense underbrush and down timber scattering fir and tamarack timber.</p>
75.00	<p>Ascend through dense undergrowth of willow.</p>
80.00	<p>Set post 5 ft. long, 4 ins. square, 2 ft. in the ground, on a S. slope in heavy fir timber and dense undergrowth for cor. to secs. 1, 6, 7 and 12 marked T 1 N S 6 on N.E., R 36 E S 7 on S.E., R 35 E S 12 on S.W., and S 1 on the N.W. faces with 5 notches on the S. and 1 notch on the N. faces.</p> <p style="padding-left: 40px;">A fir, 12 ins. diam., bears S.41°W., 50 lks. dist., marked T 1 N R 36 E S 12 B T.</p> <p style="padding-left: 40px;">A fir, 20 ins. diam., bears S.51°E., 62 lks. dist., marked T 1 N R 37 E S 7 B T.</p> <p style="padding-left: 40px;">A fir, 30 ins. diam., bears N.38°E., 51 lks. dist., marked T 1 N R 37 E S 6 B T.</p> <p style="padding-left: 40px;">A fir, 14 ins. diam., bears N.13°W., 32 lks. dist., marked T 1 N R 36 E S 1 B T.</p> <p>Land, high rough, mountainous and broken.</p> <p>Soil, rocky, 2nd rate.</p> <p>Timber, fir and tamarack.</p> <p>Soil in swamp, 1st rate.</p>
	<p>North between secs. 1 and 6.</p> <p style="text-align: right;">Var. 21°E.</p> <p>Ascend through heavy timber and dense undergrowth.</p>
10.00	<p>Descend gradually.</p>
40.00	<p>Set post, 3½ ft. long, 3 ins. square, 12 ins. in the ground on mountain side sloping N.W. in dense alder thicket and heavy timber for ¼ sec. cor marked ¼ S on the E. and W. faces</p> <p style="padding-left: 40px;">A fir, 12 ins. diam., bears N.82°W., 24 lks. dist., marked ¼ S B T.</p>