

Base Line of T. 1 N., R. 37 E.  
 Surveyed by Timothy W. Davenport, contract No. 102.  
 Dated July 20, 1863.

Chains	Thence East on South boundary of sec. 31.	
8.50	A hemlock, 24 ins. in diam.	
28.00	Spring branch, 5 lks. wide, runs N.E.	-300
40.00	Set qr. sec. post, from which,	-100
	A red fir, 7 ins. in diam., bears N.30°W., 34 lks.	
	A red fir, 5 ins. in diam., bears S.60°W., 18 lks. dist.	
80.00	Set post corner to secs. 31 and 32, on side of ridge,	-200
	from which,	
	A red fir, 12 ins. in diam., bears N.E. 10 lks. dist.	
	" " " 10 " " " " N.W. 35 " "	
	" " " 14 " " " " S.W. 36 " "	
	Var. 22° E.	
	Thence East on South boundary of sec. 32.	
22.50	Bottom of ravine and intersect creek, 25 lks. wide, runs N., water in holes. Timber of creek. Balm, willow, elder and alder.	-1000
40.00	Set qr. sec. post on the W. side of steep mountain, from which,	+1000
	A pine, 10 ins. in diam., bears N.50°W., 74 lks.	
	A red fir, 14 ins. in diam., bears S.25°W., 150 lks.	
	August 11, 1863.	
80.00	Set post corner to secs. 32 and 33 on the N. side of sharp spur, from which,	+450
	A tamarack, 10 ins. in diam., bears S.2 lks. dist.	
	" " 10 " " " " N.45°W., 20 lks. dist.	
	A tamarack, 12 ins. in diam., bears N.45°E., 26 lks.	
	Var. 19°45'E.	
	Thence East on South boundary of sec. 33.	
40.00	Set qr. sec. post on N. side of ridge, from which,	+400
	A red fir, 6 ins. in diam., bears S.65°W., 6 lks.	
	A red fir, 8 ins. in diam., bears N.40°E., 8 lks.	
80.00	Set post corner to secs. 33 and 34 on top of ridge, from which,	+800