

South Boundary of T. 2 N., R. 37 E.

Chains	
	<p>glade on ridge.</p> <p>A fir, 20 ins. diam., bears S.85°W., 295 lks. dist., marked T 1 N R 37 E S 4 B T.</p> <p>The above post is marked T 2 N S 34 on N.E., R 37 E S 3 on S.E., T 1 N S 4 on S.W., and S 33 on N.W. faces, with 3 notches on E. and W. edges.</p> <p>Land, mountainous, broken and rocky.</p> <p>Soil, rocky ridges, barren.</p> <p>Timber, fir, pine and tamarack.</p>
	<p>N.89°57'W. on true line between secs. 4 and 33.</p> <p style="text-align: center;">Var. 21°30'.</p>
3.50	<p>Enter timber.</p> <p>Descend.</p>
10.50	<p>Bottom of ravine.</p> <p>Ascend.</p>
20.00	<p>Summit glade, 2 chs. wide; descend.</p>
40.00	<p>Spring branch, course N.E. Set post, 3½ ft. long, 3 ins. square, 1½ ft. in ground, marked ¼ S for ¼ sec. cor., on West bank of said stream.</p> <p>A tamarack, 24 ins. diam., bears S.22°W., 14 lks. dist., marked ¼ S B T.</p> <p>A fir, 12 ins. diam., bears N.26°E., 13 lks. dist., marked ¼ S B T.</p> <p>Ascend up ravine through alder thicket.</p>
53.00	<p>Ascend abruptly.</p>
56.50	<p>Glade, 2 chs. wide.</p>
80.00	<p>Set post 4 ft. long, 4½ ins. square, 2 ft. in ground, for cor. to secs. 4, 5, 32 and 33 in glade sloping N.W.</p> <p>Post is marked T 2 N S 33 on N.E., R 37 E S 4 on S.E., T 1 N S 5 on S.W., and S 32 on N.W. faces, with 4 notches on E. and 2 notches on W. edges.</p> <p>A fir, 16 ins. diam., bears S.39°W., 1.00 lks. dist., marked T 1 N R 37 S 4 B T.</p> <p>A fir, 24 ins. diam., bears N.38°E., 1.30 lks. dist., marked T 2 N R 37 S 33 B T.</p>