

Resurvey of Base Line through Range 37 East.

Chains	
	<p>37 E. on N., S 34 on E. and S 33 on W. faces, with 3 notches on E. and W. faces, from which,</p> <p>A fir, 30 ins. diam., bears N.10°E., 19 lks. dist., marked T 1 N R 37 E S 34 B T.</p> <p>A fir, 24 ins. diam., bears S.15°E., 76 lks. dist., marked T 1 S R 37 E S 4 B T.</p> <p>A fir, 18 ins. diam., bears N.40°W., 10 lks. dist., marked T 1 N R 37 E S 33 B T.</p> <p>The old sec. cor., a post with 2 bearing trees, bears W., 13.00 chs. dist. I obliterate the marks on post and trees.</p> <p>Land, rough and mountainous.</p> <p>Soil, sandy loam, 2nd rate.</p> <p>Heavily timbered with fir and tamarack.</p> <p>Dense undergrowth of mountain laurel.</p>
	<p>West on Base Line on S. boundary of sec. 33.</p> <p style="text-align: center;">Var. 20$\frac{1}{4}$° E.</p> <p>Ascend through timber.</p> <p>10.00 Top of ridge, about 100 ft. above cor., course N.W.</p> <p>32.50 A spring branch, 2 lks. wide, runs N.W.</p> <p>40.00 Set a post, 3 ft. long, 3 ins. square, 24 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked B L $\frac{1}{4}$ S on N. face, from which,</p> <p style="padding-left: 40px;">A fir, 7 ins. diam., bears N.45°E., 16 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p style="padding-left: 40px;">A fir, 3 ins. diam., bears S.50°W., 17 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>I could find no trace of the old $\frac{1}{4}$ sec. cor.</p> <p>80.00 Set a post, 4 ft. long, 4 ins. square, 24 ins. in the ground, for cor. to secs. 32 and 33 marked B L T 1 N R 37 E on N., S 33 on E. and S 32 on W. faces, with 4 notches on E. and 2 notches on W. faces, from which,</p> <p style="padding-left: 40px;">A tamarack, 15 ins. diam., bears N.55°E., 15 lks. dist., marked T 1 N R 37 E S 33 B T.</p>