

Subdivisions of T. 1 N., R. 37 E.

Chains	<p>Thence I run N. 89° 34' W. on a true line between secs. 13 and 24.</p> <p>40.18 Set a basalt stone, 17x10x5 ins., 11 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face, and raised a mound of stone alongside.</p> <p>80.36 The cor. to secs. 13, 14, 23 and 24. Land, mountainous. Soil, 3rd rate. Timber, scattering pine, fir and tamarack, with dense undergrowth of mountain laurel.</p>
	<p>North between secs. 13 and 14. Var. 20° E. Through timber and brush.</p> <p>40.00 Set a basalt stone, 16x12x10 ins., 11 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, and raised a mound of stone alongside.</p> <p>80.00 Set a basalt stone, 18x14x7 ins., 12 ins. in the ground, for cor. to secs. 11, 12, 13 and 14, marked with 4 notches on S. and 1 notch on E. edges, and raised a mound of stone alongside. Land, mountainous. Soil, stony, 3rd rate. Timber, scattering pine, fir and tamarack, with dense undergrowth of mountain laurel.</p>
	<p>East on a random line between secs. 12 and 13. Var. 20 $\frac{3}{4}$° E. Through brush and timber.</p> <p>40.00 Set temporary $\frac{1}{4}$ sec. cor.</p> <p>79.82 Intersect E. boundary, 31 lks. N. of the cor. to secs. 12, 13, 7 and 18, which is a post, 4 ins. square, marked T 1 N S 7 on N.E., R 38 E S 18 on S.E., R 37 E S 13 on S.W., and S 12 on N.W. faces, with 4 notches on S and 2 notches on N. edges, from which,</p>