

## Subdivisions of T. 1 N., R. 37 E.

Chains	
	<p>for cor. to secs. 2, 3, 10 and 11, marked with 5 notches on S. and 2 notches on E. edges, and raised a mound of stone alongside.</p> <p>Land, mountainous.</p> <p>Soil, stony, 3rd rate.</p> <p>Scattering pine, fir and tamarack timber.</p> <p>Dense undergrowth of mountain laurel.</p> <p style="text-align: right;">September 2, 1882.</p>
<p>40.00</p> <p>79.90</p> <p>39.95</p> <p>79.90</p>	<p>East on a random line between secs. 2 and 11.</p> <p style="text-align: center;">Var. <math>21\frac{1}{2}^{\circ}</math>E.</p> <p>Ascend through brush.</p> <p>Set temporary <math>\frac{1}{4}</math> sec. cor.</p> <p>Intersect 40 lks. S. of the cor. to secs. 1, 2, 11 and 12.</p> <p>Thence I run</p> <p>S. <math>89^{\circ}43'</math>W. on a true line between secs. 2 and 11.</p> <p>Set a basalt stone, 15x10x5 ins., 10 ins. in the ground, for <math>\frac{1}{4}</math> sec. cor. marked <math>\frac{1}{4}</math> on N. face, and raised a mound of stone alongside.</p> <p>The cor. to secs. 2, 3, 10 and 11.</p> <p>Land, mountainous.</p> <p>Soil, stony, 3rd rate.</p> <p>Scattering pine, fir and tamarack timber.</p> <p>Dense undergrowth of mountain laurel.</p>
<p>25.00</p> <p>40.00</p> <p>80.36</p>	<p>North on a random line between secs. 2 and 3.</p> <p style="text-align: center;">Var. <math>21\frac{1}{2}^{\circ}</math>E.</p> <p>A brook, 4 lks. wide, runs S.W.</p> <p>Set temporary <math>\frac{1}{4}</math> sec. cor.</p> <p>Intersect N. boundary, 25 lks. E. of the cor. to secs. 2, 3, 34 and 35, which is a post, 4 ins. square, marked T 2 N S 35 on N.E., R 37 E S 2 on S.E., T 1 N S 3 on S.W., and S. 34 on N.W. faces, with 2 notches on E. and 4 notches on W. edges, from which,</p>