

Subdivisions of T. 1 N., R. 37 E.

Chains 40.00	Set a basalt stone, 14x10x4 ins., 9 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, and raised a mound of stone alongside.
80.00	Set a basalt stone, 16x12x12 ins., 11 ins. in the ground, for cor. to secs. 9, 10, 15 and 16, marked with 4 notches on S. and 3 notches on E. edges, and raised a mound of stone alongside. Land, mountainous. Soil, stony, 3rd rate. Scattering fir and pine timber. Dense undergrowth of mountain laurel, young fir and pine.
	East on a random line between secs. 10 and 15. Var. $20\frac{1}{4}^{\circ}$ E. Ascend through brush.
30.00	Top of ridge, about 400 ft. above cor., course N.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
79.88	Intersect 37 lks. N. of the cor. to secs. 10, 11, 14 and 15. Thence I run N. $89^{\circ}44'$ W. on a true line between secs. 10 and 15.
39.99	Set a basalt stone, 14x10x6 ins., 9 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone alongside.
79.88	The cor. to secs. 9, 10, 15 and 16. Land, mountainous. Soil, 2nd rate. Scattering fir, pine timber with dense undergrowth of mountain laurel, young fir and pine. September 4, 1882.
	North between secs. 9 and 10. Var. $20\frac{1}{4}^{\circ}$ E. Descend about 300 ft. to