

## Subdivisions of T. 1 N., R. 37 E.

Chains	
35.00	Bottom of gulch, about 150 ft. below ridge. A brook, 5 lks. wide, runs W.
37.00	Leave heavy and enter scattering timber.
40.00	Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S on W. face. Dug pits, 18x18x12 ins., N. and S. of cor., $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around post.
80.00	A point about 1000 ft. above brook. Set a basalt stone, 18x12x6 ins., 12 ins. in the ground, for cor. to secs. 28, 29, 32 and 33, marked with 1 notch on S. and 4 notches on E. edges, and raised a mound of stone alongside.
	Land, mountainous.
	Soil, 2nd rate.
	Heavily timbered with fir and tamarack on S. 37.00 chs. scattering timber on remainder.
<hr/>	
	East on a random line between secs. 28 and 33.
	Var. $21\frac{1}{4}^{\circ}$ E.
	Descend about 150 ft. to
20.00	Bottom of gulch, course S.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
41.00	Top of ridge, about 100 ft. above gulch, course S.
60.00	Bottom of gulch about 100 ft. below ridge, course S.
73.00	Top of ridge about 100 ft. above gulch, course N.W.
79.66	Intersect 25 lks. N. of the cor. to secs. 27, 28, 33 and 34.
	Thence I run
	N. $89^{\circ}49'$ W. on a true line between secs. 28 and 33.
39.83	Set a basalt stone, 14x8x6 ins., 9 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face, and raised a mound of stone alongside.
79.66	The cor. to secs. 28, 29, 32 and 33.
	Land, mountainous.