

Subdivisions of T. 1 N., R. 37 E.

Chains	West on a random line between secs. 18 and 19. Var. $20\frac{1}{2}^{\circ}$ E.
	Descend about 75 ft. to
0.75	Bottom of gulch, course S.E.
	Ascend about 700 ft. to
28.50	Top of ridge, course S.E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
50.00	Bottom of canyon about 1000 ft. below ridge. A spring branch, 3 lks. wide, runs S.E.
103.35	Intersect W. boundary, 12 lks. S. of the cor. to secs. 18, 19, 13 and 24, which is a post, 4 ins. square, marked T 1 N S 18 on N.E., R 37 E S 19 on S.E., R 36 E S 24 on S.W., and S 13 on N.W. faces, with 3 notches on N. and S. edges, from which, A pine, 24 ins. diam., bears N.50°E., 119 lks. dist., marked T 1 N R 37 E S 18 B T. A fir, 24 ins. diam., bears N.61°W., 80 lks. dist., marked T 1 N R 36 E S 13 B T. A pine, 16 ins. diam., bears S.67°W., 62 lks. dist., marked T 1 N R 36 E S 24 B T. Thence I run S.89°56'E. on a true line between secs. 18 and 19..
63.35	Set a basalt stone, 14x14x8 ins., 9 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone alongside.
103.35	The cor. to secs. 17, 18, 19 and 20. Land, mountainous. Soil, stony, 3rd rate. Scattering fir, pine and tamarack timber. Dense undergrowth of buck brush.
	North between secs. 17 and 18. Var. $20\frac{1}{2}^{\circ}$ E.
	Ascend.
40.00	Set a basalt stone, 14x10x6 ins., 9 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, and raised a mound