

Resurvey of South Bdy. of T. 2 N., R. 37 E.

Chains	N.89°16'W. on old township line between secs. 4 and 33. Over rocky prairie.
3.75	Descend over rolling ground through heavy timber and dense undergrowth, bears N. and S.
4.25	Back Mt. pack trail, bears N.60°E., S.60°W.
10.25	Dry bed of stream, 3 lks. wide, in ravine 50 ft. deep, course S.30°E. Large spring about 5.00 chs. S. of this point. Ascend gradually.
21.10	Summit of divide between Meacham Creek and Umatilla River, 50 ft. above dry bed of stream, course N.30°E., S.30°W. Descend steep W. slope.
39.50	Foot of hill, 400 ft. below top of divide, bears N. and S. Creek, 5 lks. wide, swift current, stony bottom, course N.10°E. Ascend.
40.31	Intersect old $\frac{1}{4}$ sec. cor., which is a post nearly burned away and witnessed as described by the surveyor general, with the exception of the S.W. bearing tree, which has been destroyed. I set a basalt stone, 15x12x5 ins., 10 ins. in the ground, at the same point, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face, from which, A tamarack, 24 ins. diam., bears S.22°W., 14 lks. dist., marked $\frac{1}{4}$ S 4 B T. The other witness tree bears as stated by the surveyor general S.89°33'W. Over rolling ground.
67.00	Leave heavy timber and enter scattering pine and fir forest, bears N. and S.
68.25	Top of ridge, 200 ft. high, bears N. and S. Descend.
76.50	Enter sheep corral, bears N. and S.
77.25	Leave sheep corral, bears N. and S.
80.36	Intersect old cor. of secs. 4, 5, 32 and 33, which is a post, badly decayed, marks obliterated and witnessed as described by the surveyor general with the exception