

Bet. Rs. 29 & 30, E., T.1 S., W.M.

Chains		Feet
59.00	A ravine brs. E.	130
80.00	Set a stone, 22 x 7 x 5 on S.E. hillside for Cor. to Secs. 12, 13, 7 & 18. Land; high and broken, 2nd & 3rd rate, part worthless.	
N. along the E. Bdy. of Sec. 12		
Var. 19° 02' E.		
25.00	A ravine brs. N.E.	250
40.00	Set a stone, 24 x 8 x 5 on N.E. hillside for $\frac{1}{4}$ Sec. Cor. Var. 19° 00' E.	40
61.00	Butter Creek, 30 lks. wide, runs N.W.	80
74.00	On spur brs. W.	100
80.00	Set a stone, 18 x 10 x 7 on N.W. side of spur for Cor. to Secs. 1, 12, 6 & 7. Land; high, broken bluffs, 2nd & 3rd rate, a small part on the creek is first rate.	20
N. on the E. Bdy. of Sec. 1		
Var. 22° 07' E.		
2.00	A ravine brs. W.	20
14.00	A spur brs. S.W.	100
23.50	A ravine brs. S.W.	100
40.00	Set a stone, 18 x 12 x 5 on spur for $\frac{1}{4}$ Sec. Cor. Var. 22° 00' E.	220
51.50	A ravine brs. W.	80
78.67	Intersected the Base Line at a point 6 chs. and 57 lks. W. of mound, the Cor. to Secs. 35 & 36, Tp. 1 N., R. 29 E. Set a stone, 30 x 7 x 6 at point of intersection for Cor. to Tp. 1 S., Rs. 29 & 30 E. Raised a mound of stone as per instructions.	160
Var. 21° 55' E.		
Land; high, broken bluffs, 3rd rate, part worthless.		
Sept. 11, 1871		