

3.

Between Tps. 1 & 2 S., R. 30 E., W.M.  
 Surveyed by same Deputies, under same Contract.  
 Under same date.

Chains		Feet
	From the Cor. to Tps. 1 & 2 S., Rs. 30 & 31 E. I run W. on a random line bet. said Tps. <span style="float: right;">Var. 21° 45' E.</span> I set temp. half mile and mile posts at every 40 and 80 chs. and at 5 miles, 78 chains and 47 links, to a point, 1 ch., 6 lks. S. of the Cor. to Tps. 1 & 2 S., Rs. 29 & 30 E. Therefore the correction will be 17 2/3 lks. per mile.	
	From the Cor. to Tps. 1 & 2 S., Rs. 29 & 30 E., I run S. 89° 53' E. on a true line bet. Secs. 6 & 31. <span style="float: right;">Var. 20° 21' E.</span>	
2.00	County road brs. N.E. & S.W. Foot of hill brs. N.E. & S.W.	
38.47	Set a stone, 20 x 8 x 4 on top of hill for 1/4 Sec. Cor. A small table land. <span style="float: right;">Var. 21° 33' E.</span>	+260
78.47	Set a stone, 20 x 7 x 5 for Cor. to Secs. 5, 6, 31 & 32. Land; first half mile broken hillside, last half mile level table land. 2nd & 3rd rate.	
	S. 89° 53' E. on a true line bet. Secs. 5 & 32. <span style="float: right;">Var. 21° E.</span>	
5.00	Begin descent	
25.00	A ravine brs. N.E.	-200
38.00	Foot of hill, brs. N. & S.	-100
40.00	Set a stone, 20 x 8 x 4 in canyon for 1/4 Sec. Cor. <span style="float: right;">Var. 22° 28' E.</span>	
65.00	Top of hill	+290
75.00	Begin to descend	
80.00	Set a stone, 24 x 7 x 5 on S.E. hillside for Cor. to Secs. 4, 5, 32 and 33. Land; high hills and broken, 2nd & 3rd rate.	-15
	S. 89° 53' E. on true line bet. Secs. 4 & 33.	