

Township 1 S., R.30 E., W.M.

Chains		Feet
40.00	Set a stone, 20 x 6 x 5 on S.E. hillside for $\frac{1}{4}$ Sec. Cor. Var. 19° 47' E.	-250
49.75	A ravine brs. N.E.	-80
61.00	On spur extending N.E.	+60
68.00	Foot of hill brs. N. & S.	-120
73.60	Butter Creek, 30 lks. wide, runs N.	
76.50	Foot of ledge of basalt rock, 25 ft. high, brs. N. & S.	
80.00	Set a stone, 18 x 8 x 6 on a bench for Cor. to Secs. 3, 4, 33 & 34. Land; very hilly and broken, 2nd & 3rd rate. Small part on the Creek is level and first rate and is good for farm- ing.	+30
S. 89° 53' E. on a true line bet. Secs. 3 & 34. Var. 22° 16' E.		
1.00	Creek road brs. N. & S.	
40.00	Set a stone, 20 x 10 x 3 on top of hill for $\frac{1}{4}$ Sec. Cor. Var. 22° 28' E.	+450
79.00	A ravine brs. N.	-70
80.00	Set a stone, 24 x 6 x 5 on E. side of ravine for Cor. to Secs. 2, 3, 34 & 35. Land; high, broken bluffs, 3rd rate, part worthless.	
S. 89° 53' E. on a true line bet. Secs. 2 & 35. Var. 26° 26' E.		
5.00	On spur, brs. N.E.	+50
34.50	A ravine, brs. N.E.	-250
40.00	Set a stone, 18 x 8 x 6 on N. point of spur for $\frac{1}{4}$ Sec. Cor. Var. 23° 14' E.	+60
50.00	A canyon, brs. N.	-80
80.00	Set stone, 16 x 9 x 6 on W. side of hill for Cor. to Secs. 1, 2, 35 & 36 Land; high, broken bluffs, 2nd & 3rd rate.	+28
S. 89° 53' E. on a true line bet. Sec. 1 & 36.		
5.00	On table land Var. 20° 18' E.	+30