

Subdivisional Lines, T.1 S., R.30 E., W. M.
 As surveyed by Geo. Williams & Geo. S. Pershin, U.S. Deputy Surveyors
 Under their Contract No. 154,
 Dated June 6, 1871.

Chains	Subdivisional Lines commenced Oct. 26, 1871.	Feet
	From the Cor. to Secs. 1, 2, 35 & 36 on S. Bdy. of Tp., I run, N. bet. Secs. 35 & 36. Var. 23°12'E.	
17.00	A ravine, brs. N.W.	50
22.00	A small ravine, brs. W.	
26.00	A ravine, brs. S.W.	
40.00	Set stone, basalt, 17 x 8 x 6 on S. hillside for $\frac{1}{4}$ Sec. Cor. Var. 21°23'E.	50
42.00	Top of hill.	5
61.00	A ravine, brs. S.E.	50
80.00	Set stone, basalt, 18 x 7 x 6 on E. hillside for Cor. to Secs. 25, 26, 35 & 36. Land; high & broken, 2nd & 3rd rate.	30
	E. on random line bet. Secs. 25 & 36. Var. 17°24'E.	
40.00	Set stake for temp. $\frac{1}{4}$ Sec. Cor.	
80.20	Intersected E. Bdy. of T. at Cor. to Secs. 25 & 36, from which Cor., I run W. on true line bet. Secs. 25 & 36. Var. 22°20'E.	
16.00	A spur, extending N.W.	30
24.00	A ravine, brs. N.W.	50
40.10	Set stone, 18 x 8 x 6 on N. point of spur, for $\frac{1}{4}$ Sec. Cor. Var. 20°18'E.	50
49.50	A ravine, brs. N.W.	40
57.00	A spur, brs. N.W.	30
65.50	A ravine, brs. N.W.	40
72.00	A spur, brs. N.W.	40
78.00	A ravine, brs. N.	40
70.20	The Cor. to Secs. 25, 26, 35 & 36. Land; high, very much broken, 2nd & 3rd rate.	20
	N. bet. Secs. 25 & 26. Var. 17°24'E.	
22.00	A canyon, brs. W.	80
40.00	Set stone, 18 x 10 x 4 on top of rise for $\frac{1}{4}$ Sec. Cor.	180
65.00	A ravine, brs. N.W. Var. 22°20'E.	100
71.00	On spur, brs. N.W.	20