

9.  
Tp. 1 S., R.30 E., W.M.

Chains		Feet
	Var. 21° 48' E.	
27.00	Highest point on line	+50
40.10	Set a stone, 22 x 10 x 4 for $\frac{1}{4}$ Sec. Cor.	-40
	Var. 22° 54' E.	
53.00	A shallow ravine, brs. S.	-20
80.20	The Cor. to Secs. 13, 14, 23 & 24	+40
	Land; slightly rolling, excellent quality of 2nd rate.	
	Oct. 26, 1871	
N. bet. Secs. 13 & 14.		
	Var. 21° 22' E.	
40.00	Set a stone, 19 x 10 x 5 for $\frac{1}{4}$ Sec. Cor.	+ 30
	Var. 21° 34' E.	
55.00	Highest point.	+15
80.00	Set a stone, 18 x 6 x 6 for Cor. to Secs. 11, 12, 13 & 14	-20
	Land; nearly level, good 2nd rate, would be good for farming if climate more favorable.	
E. on a random line bet. Secs. 12 & 13.		
	Var. 19° 56' E.	
40.00	Set a stake for Temp. $\frac{1}{4}$ Sec. Cor.	
80.10	Intersected E. Bdy. of Tp., 16 lks. N. of Cor. to Secs. 12 & 13, from which Cor., I run, N.89° 53' W. on a true line bet. Secs. 12 & 13.	
	Var. 22° 00' E.	
40.05	Set a stone, 24 x 8 x 4 for $\frac{1}{4}$ Sec. Cor.	+25
	Var. 20° 36' E.	
80.10	The Cor. to Secs. 11, 12, 13 & 14.	
	Land; nearly level, excellent quality 2nd rate.	
N. bet. Secs. 11 & 12.		
	Var. 19° 56' E.	
22.50	A ravine, brs. N.E.	-30
40.00	Set a stone, 17 x 8 x 5 for $\frac{1}{4}$ Sec. Cor.	+30
	Var. 21° 00' E.	