

T.1 S., R.30 E., W.M.

Chains		Feet
50.00	Highest point	+ 10
64.50	Road from Butter Creek to Burch Creek, brs. N.W. & S.E.	-20
80.00	Set a stone, 22 x 7 x 4 for Cor. to Secs. 1, 2, 11 & 12 Land; undulating, excellent 2nd rate.	-40
East on a random line bet. Secs. 1 & 12. Var. 20° 28' E.		
40.00	Set a stake for temp. $\frac{1}{4}$ Sec. Cor.	
79.72	Intersected E. Bdy. of T., 23 lks. S. of Cor. to Secs. 1 & 12, from which Cor. I run S. 89° 50' W. on a true line bet. Secs. 1 & 12. Var. 22° 28' E.	
39.86	Set a stone, 19 x 7 x 6 for $\frac{1}{4}$ Sec. Cor. Var. 22° 33' E.	-40
79.72	The Cor. to Secs. 1, 2, 11 & 12 Land; undulating, excellent 2nd rate.	+50
N. bet. Secs. 1 & 2. Var. 20° 28' E.		
7.25	A ravine brs. E.	-25
40.00	Set a stone, 22 x 8 x 5 for $\frac{1}{4}$ Sec. Cor.	+20
78.83	Appointment Base Line, 12 chs. & 28 lks. W. of mound, Cor. to Secs. 34 & 35, T.1 N. R. 30 E. Set a stone, 25 x 11 x 2 at point of intersection for Cor. to Secs. 1 & 2. Var. 20° 35' E. Land; undulating, excellent 2nd rate. Oct. 27, 1871	+30
N. bet. Secs. 34 & 35 Var. 26° 26' E.		
36.00	A canyon brs. N.W.	-120
40.00	Set a stone, 18 x 6 x 5 on S. hillside for $\frac{1}{4}$ Sec. Cor. Var. 24° 48' E.	+80
66.00	A ravine brs. S.W.	-20