

T.1 S., R.30 E., W.M.

Chains		Feet
25.00	Top of hill	+240
40.06	Set a stone, 24 x 6 x 5 on W. hillside for $\frac{1}{4}$ Secs. Cor. Var. 21° 22' E.	
68.00	A ravine brs. S.W.	-220
80.12	The Cor. to Secs. 22, 23, 26 & 27. Land; high hills and spurs, 2nd and 3rd rate, part worth- less.	+70
N. bet. Secs. 22 & 23. Var. 20° 50' E.		
24.00	Top of hill	+200
40.00	Set a stone, 18 x 6 x 6 on N. hillside for $\frac{1}{4}$ Secto Cor. Secs. 14, 15, 22 & 23 Var. 22° 22' E.	-120
54.00	A ravine brs. W.	-120
80.00	Set a stone, 17 x 10 x 8 on N.W. hillside for Cor. to Secs. 14, 15, 22 & 23 Land; high hills, 2nd & 3rd rate, part worthless	+150
E. on a random line bet. Secs. 14 & 23. Var. 25° 13' E.		
40.00	Set a stake for temp. $\frac{1}{4}$ Sec. Cor.	
79.93	Intersected N.&.S. line, 8 lks. N. of Cor. to Secs. 13, 14 23 & 24, from which Cor., I run N. 89° 57' W. on a true line bet. Secs. 14 & 23. Var. 21° 22' E.	
22.00	A ravine brs. S.E.	+30
39.96	Set a stone, 19 x 10 x 5 for $\frac{1}{4}$ Sec. Cor. Var. 21° 47' E;	+30
79.92	The Cor. to Secs. 14, 15, 22 & 23 Land; eastern part undulating, western part broken 2nd rate. Oct. 28, 1871	-180
N. bet. Secs. 14 & 15. Var. 25° 13' E.		
9.50	A canyon brs. S.W.	+120