

T.1 S., R.30 E., W. M.

Chains		Feet
40.00	Set stone, 17 x 8 x 5 for $\frac{1}{4}$ Sec. Cor. Var.21°12' E.	+ 15
70.00	Highest point	+ 30
78.54	A point on Base Line, 12 chs. & 25 lks. from one mound & 8 chs. & 25 lks. from another mound, both marked as Cors. to Secs. 33 & 34, T.1 N.,R.30 E. Set stone, 18 x 8 x 5 at point of intersection for Cor. to Secs. 2 & 3. Var.20°22' E. Land; undulating, good 2nd rate. Oct. 30, 1871.	
	N. bet. Secs. 33 & 34. Var.22°16'E.	
40.00	Set stone, 22 x 8 x 4 for $\frac{1}{4}$ Sec. Cor. Samuel G. Lightfoot's house brs. S.80°30'W. Var.20°55'E.	
46.00	A ravine brs. W.	- 25
58.00	Samuel G. Lightfoot's house brs. S.26°30'W.	+ 80
80.00	Set stone, 22 x 9 x 6 on W. hillside for Cor. to Secs. 27, 28, 33 & 34. Land; somewhat broken, 2nd rate.	- 30
	E. on random line bet. Secs. 27 & 34. Var.21°33'E.	
40.00	Set stake for temp. $\frac{1}{4}$ Sec. Cor.	
80.18	Intersected N. & S. line, 45 lks. N. of Cor. to Secs. 26, 27, 34 & 35, from which Cor., I run N.89°41'W. on true line bet. Secs. 27 & 34. Var.23°08' E.	
15.00	Top of hill.	+ 40
40.09	Set stone, 21 x 7 x 4 on N.W. hillside for $\frac{1}{4}$ Sec. Cor. Var.23°46'E.	- 80
80.18	The Cor. to Secs. 27, 28, 33 & 34. Land; high & broken, 2nd & 3rd rate, part worthless.	- 300
	N. bet. Secs. 27 & 28. Var.21°33'E.	