

T.1 S., R.30 E., W.M.

Chains		Feet
	East on a random line bet. Secs. 10 & 15. Var. 21° 00' E.	
40.00	Set a stake for temp. $\frac{1}{4}$ Sec. Cor.	
79.96	Intersected N.&S. line, 21 lks. S. of the Cor. to Secs. 10, 11, 14 & 15, from which Cor., I run S.89° 51' W. on a true line bet. Secs. 10 & 15. Var. 22° 07' E.	
34.50	A ravine brs. N.W.	-200
39.98	Set a stone, 22 x 8 x 4 on N.E. side of spur for $\frac{1}{4}$ Sec. Cor. Var. 21° 12' E.	+30
44.50	A spur brs. N.	+10
60.25	A ravine brs. N.	-80
79.96	The Cor. to Secs. 9, 10, 15 and 16. Land; high and broken, 2nd & 3rd rate.	+70
	N. bet. Secs. 9 & 10. Var. 21° 00' E.	
17.50	A canyon brs. W.	-180
40.00	Set a stone, 18 x 10 x 5 on W. hillside for $\frac{1}{4}$ Secs. Cor. Var. 23° 03' E.	+170
80.00	Set a stone, 22 x 8 x 6 on W. hillside for Cor. to Secs. 3, 4, 9 & 10 Land; hilly and broken, 2nd & 3rd rate.	-40
	E. on a random line bet. Secs. 3 & 10. Var. 22° 57' E.	
40.00	Set a stake for temp. $\frac{1}{4}$ Sec. Cor.	
79.88	Intersected N.&S. line at Cor. to Secs., 2, 3, 10 and 11, from which Cor., I run W. on a true line bet. Secs. 3 & 10. Var. 21° 53' E.	
39.94	Set a stone, 18 x 10 x 4 on a mound for $\frac{1}{4}$ Secs. Cor. Var. 20° 42' E	+70
79.88	The Cor. to Secs. 3, 4, 9 & 10. Land; high, somewhat broken, 2nd rate.	-180