

T.1 S., R.30 E., W.M.

Chains		Var. 19° 33' E.	Feet
52.00	Top of ridge, brs. N.&.S.		+100
67.50	A ravine, brs. N.E.		-220
80.28	The Cor. to Secs. 28, 29, 32 & 33		+120
	Land; hilly and broken, 2nd rate, small part on Creek is 1st rate.		
N. bet. Secs. 28 & 29.			
		Var. 21° 16' E.	
34.00	Top of ridge, brs. N.E. & S.W.		+ 50
40.00	Set a stone, 20 x 7 x 5 on W. side of ridge for $\frac{1}{4}$ Sec. Cor.		50
		Var. 21° 28' E.	
50.50	Foot of hill, brs. N.E. & S.W.		-200
51.25	Brook, 5 lks. wide, runs N.E.		
52.50	Road brs. N.E. & S.W.		
80.00	Set stone, 18 x 10 x 8 on S.E. hillside for Cor. to Secs. 20, 21, 28 & 29.		
	Land; hilly, 2nd & 3rd rate.		
East on a random line bet. Secs. 21 & 28.			
		Var. 18° 10' E.	
49.00	Set a stake for temp. $\frac{1}{4}$ Sec. Cor.		
80.12	Intersected N.&.S. line, 28 lks. N. of Cor. to Secs. 21, 22, 27 & 28, from which Cor.,		
	I run		
	N. 89° 48' W. on a true line bet. Secs. 21 & 28.		
		Var. 19° 18' E.	
32.00	Foot of hill, brs. N. & S.		-200
37.50	Butter Creek, 30 lks. wide, runs N.		
40.06	Set a stone, 16 x 10 x 5 for $\frac{1}{4}$ Sec. Cor.		
	John H. Frenche's house brs. S. 27° 30' E., 350 lks. dist.		
		Var. 14° 18' E.	
42.25	County Road brs. N.E. & S.W.		+ 20
80.12	The Cor. to Secs. 20, 21, 28 & 29.		+200
	Land; hilly & broken, 2nd & 3rd rate, part on Creek is 1st rate.		
	Timber; only underbrush on creek.		