

T. 1 S., R. 30 E., W.M.

Chains		Feet
80.00	Set a stone, 18 x 8 x 6 on S.W. hillside for Cor. to Secs. 9, 10, 16 & 17. Land; hilly and broken, 2nd & 3rd rate. Timber; a few trees and brush on creek	+200
<hr/>		
	East on a random line bet. Secs. 9 & 16. Var. 21° 52' E.	
40.00	Set a stake for temp. $\frac{1}{4}$ Sec. Cor.	
80.46	Intersected N. & S. line, 23 lks. N. of Cor. to Secs. 9, 10, 15 & 16, from which Cor., I run N. 89° 50' W. on a true line bet. Secs. 9 & 16. Var. 21° 00' E.	
27.50	A canyon brs. S.W.	-200
40.23	Set a stone, 16 x 12 x 6 on S.E. hillside for $\frac{1}{4}$ Sec. Cor. Var. 19° 42' E.	+100
53.50	A ravine brs. S.	+ 20
64.00	A ravine brs. S.	+ 10
80.46	The Cor. to Secs. 8, 9, 16 & 17. Land; hilly and broken, 2nd & 3rd rate.	+ 20
<hr/>		
	N. bet. Secs. 8 & 9. Var. 21° 52' E.	
	Along W. hillside.	
25.00	Begin to ascend	+100
37.00	A ravine brs. W.	-100
40.00	Set a stone, 22 x 6 x 5 on S. hillside for $\frac{1}{4}$ Sec. Cor. Var. 20° 06' E.	+ 60
68.00	A ravine brs. S.W.	- 20
80.00	Set a stone, 18 x 10 x 5 on W. hillside for Cor. to Secs. 4, 5, 8 & 9. Land; high and broken, 2nd & 3rd rate.	+100
<hr/>		
	East on a random line bet. Secs. 4 & 9. Var. 23° 11' E.	