

T. 1 S., R. 30 E., W.M.

Chains		Feet
40.00	Set a stake for temp. $\frac{1}{4}$ Sec. Cor.	
80.28	Intersected N. & S. line, 24 lks. S. of Cor. to Secs. 3, 4, 9 and 10, from which Cor., I run S. $89^{\circ} 50'$ W. on a true line bet. Secs. 4 & 9. Var. $22^{\circ} 57'$ E.	
3.00	A ravine brs. S.W.	- 10
40.14	Set a stone, 18 x 7 x 6 for $\frac{1}{4}$ Sec. Cor. Var. $21^{\circ} 36'$ E.	+ 50
80.28	The Cor. to Secs. 4, 5, 8 & 9. Land; high, somewhat broken, 2nd rate.	-120
	N. bet. Secs. 4 & 5. Var. $23^{\circ} 11'$ E.	
15.50	A ravine brs. S.W.	- 60
40.00	Set a stone, 18 x 9 x 5 for $\frac{1}{4}$ Sec. Cor. Var. $21^{\circ} 06'$ E.	+140
70.00	Highest point	+ 20
79.14	A point on Base Line, 12 chs. and 94 lks. W. of one mound and 7 chs. and 15 lks. W. of another mound, both marked for Cor. to Secs. 31 & 32, T. 1 N., R. 30 E.. Set a stone, 20 x 6 x 5 at point of intersection for Cor. to Secs. 4 & 5. Var. $21^{\circ} 00'$ E. Land; high and rolling, good 2nd rate. Nov. 3, 1871	+ 30
	N. bet. Secs. 31 & 32. Var. $20^{\circ} 18'$ E.	
30.00	Begin to descend	
40.00	Set a stone, 20 x 8 x 5 on N.W. hillside for $\frac{1}{4}$ Sec. Cor. Var. $22^{\circ} 28'$ E.	- 40
65.50	County Road from Butter Creek to little Butter Creek brs. N.E. and S.W.	-300
67.00	Bottom of Canyon brs. N.E.	- 10