

T.1 S., R.30 E., .W.M.

Chains		Feet
	N. bet. Secs. 29 & 30.	
	Var. 19° 08' E.	
17.00	Top of hill.	+180
40.00	Set a stone, 17 x 7 x 6 on N. side of hill for $\frac{1}{4}$ Sec. Cor.	-260
	Var. 19° 50' E.	
49.00	A canyon brs. E.	-100
62.00	A spur brs. S.E.	+ 80
69.50	A ravine brs. S.E.	- 20
80.00	Set a stone, 20 x 8 x 4 on S. hillside for Cor. to Secs. 19, 20, 29 & 30.	+170
	Land; high hills, 2nd & 3rd rate, part worthless.	
	East on a random line bet. Secs. 20 & 29.	
	Var. 19° 43' E.	
40.00	Set a stake for temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersected N. & S. line, 10 lks. N. of Cor. to Secs. 20, 21, 28 & 29, from which Cor.,	
	I run	
	N. 89° 56' W. on a true line bet. Secs. 20 & 29	
	Var. 18° 10' E.	
20.00	On spur brs. S.	+200
39.75	A ravine brs. S.	-250
40.00	Set a stone, 16 x 7 x 6 on W. side of ravine for $\frac{1}{4}$ Sec. Cor.	+ 10
	Var. 20° 55' E.	
63.00	A ravine brs. S.	+200
80.00	The Cor. to Secs. 19, 20, 29 & 30	+ 20
	Land; high and much broken, 3rd rate, part worthless.	
	West on a random line bet. Secs. 19 & 30.	
	Var. 19° 43' E.	
40.00	Set a stake for temp. $\frac{1}{4}$ Sec. Cor.	
78.45	Intersected W. Bdy. of Tp., 53 lks. S. of Cor. to Secs. 19 and 30, from which Cor.	
	I run	