

T. 1 S., R.30 E., W.M.

Chains		Feet
	Var. 21° 52' E.	
14.50	A ravine brs. S.	-170
30.00	Top of ridge brs. N. & S.	+180
39.75	Set a stone, 24 x 6 x 5 on S.W. hillside for $\frac{1}{4}$ Sec. Cor.	-100
	Var. 21° 08' E.	
74.50	Foot of hill brs. N.W. & S.E.	-180
76.50	Butter Creek, 28 lks. wide, runs N.W.	
79.50	The Cor. to Secs. 7, 8, 17 & 18	+ 10
	Land; hilly and broken, 2nd & 3rd rate, small part on the Creek first rate.	
	W. on a random line bet. Secs. 7 & 18.	
	Var. 20° 58' E.	
40.00	Set a stake for temp. $\frac{1}{4}$ Sec. Cor.	
78.04	Intersected W. Bdy. of Tp., 78 lks. S. of Cor. to Secs. 7 and 18, from which Cor., I run S. 89° 27' E. on a true line bet. Secs. 7 & 18.	
	Var. 19° 02' E.	
19.50	A ravine brs. N.E.	+250
38.04	Set a stone, 18 x 14 x 3 on N. point of spur for $\frac{1}{4}$ Sec. Cor.	
	Var. 21° 30' E.	
48.00	A ravine brs. N.E.	-150
78.04	The Cor. to Secs. 7, 8, 17 and 18	-200
	Land; high broken bluffs, 2nd & 3rd rate.	
	Nov. 6, 1871	
	N. bet. Secs. 7 & 8.	
	Var. 20° 58' E.	
2.50	Butter Creek, 34 lks. wide, runs N.W.	
4.50	Foot of hill, N.W. & S.E.	
37.00	A ravine brs. S.W.	+180
40.00	Set a stone, 18 x 10 x 6 on S. hillside for $\frac{1}{4}$ Sec. Cor.	+ 30
	Var. 22° 08' E.	
51.00	Top of hill	+160