

T. 1, R. 30 E., W.M.

Chains		Feet
63.50	A ravine brs. W.	-200
80.00	Set a stone, 18 x 6 x 6 on W. hillside for Cor. to Secs. 5, 6, 7 & 8.	+120
	Land; hilly and broken, small part on the Creek is first rate, remainder 2nd & 3rd rate, and part worthless.	
	Timber; a few cotton-wood trees and a growth of willow & alder brush along the creek is the only timber.	
	E. on a random line bet. Secs. 5 & 8.	
	Var. 23° 04' E.	
40.00	Set a stake for temp. $\frac{1}{4}$ Sec. Cor.	
79.80	Intersected N.&S. line, 24 lks. N. of Cor. to Secs. 4, 5, 8 & 9, from which Cor.,	
	I run	
	N. 89° 51' W. on a true line bet. Secs. 5 & 8.	
	Var. 23° 11' E.	
7.25	A canyon brs. S.W.	-120
23.00	Top of hill	+280
39.90	Set a stone, 16 x 10 x 6 on W. hillside for $\frac{1}{4}$ Sec. Cor.	- 50
79.80	The Cor. to Secs. 5, 6, 7 & 8. Var. 21° 14' E.	-200
	Land; high and somewhat broken, 2nd & 3rd rate.	
	W. on a random line bet. Secs. 6 & 7.	
	Var. 23° 04' E.	
40.00	Set a stake for temp $\frac{1}{4}$ Sec. Cor.	
78.56	Intersected W. Bdy. of Tp., 94 lks. S. of the Cor. to Sec. 6 & 7, from which Cor.,	
	I run	
	S. 89° 20' E. on a true line bet. Secs. 6 & 7.	
	Var. 22° 07' E.	
22.50	Top of hill	+250
38.56	Set a stone, 18 x 7 x 5 on E. hillside for $\frac{1}{4}$ Sec. Cor.	-19
	Var. 18° 58' E.	
69.50	A ravine brs. S.	- 90
78.56	The Cor. to Secs. 5, 6, 7 & 8.	+150