

T. 1 S., R. 30 E. W.M.

Chains		Feet
	Land; high and very much broken, 2nd & 3rd rate, part worthless.	
	N. bet. Secs. 5 & 6. Var. 23° 04' E.	
6.25	A ravine brs: W.	-100
40.00	Set a stone, 24 x 7 x 5 on W. hillside for $\frac{1}{4}$ Sec. Cor. Var. 21° 36' E.	+300
60.00	Highest point	+ 40
79.43	A point on Base Line, 6 chs. and 53 lks. W. of Cor. to Tps. 1 N., Rs. 29 & 30 E., Set a stone, 24 x 7 x 5 at point of intersection for Cor. to Secs. 5 & 6. Var. 20° 56' E.	
	Land; high and broken, 2nd rate. I make diligent search and can find but one marked corner at this place. I now proceed W. one mile and after dili- gent search can find but one marked corner (a mound with stake) for Secs. 35 & 36, Tp.1 N., R. 29 E., near which is the Cor. to Tps. 1 S. Rs. 29 & 30 E. It is evident there has been some irregularity in marking the Base Line.	
	Nov. 7, 1871.	
	General Description.	
	The land in this Tp. is principally Second rate, one-fourth third rate and one eighth worthless, second and third rate lands produce excellent Bunch Grass and are there- fore valuable for grazing purposes; a small part along the Creek is first rate and good for farming.	
	The surface in the North-eastern part is part level and part part undulating; in the Southwestern part and along the Creek it is very hilly and broken.	
	Timber, a few cotton-wood trees and a thick growth of wil- low and alder brush along the Creek is the only timber.	
	Butter Creek, running thru the Western part, and a number of springs in other parts of the Tp. afford water for stock.	