

T. 1 S., R. 31 E., W.M.

Chains		Feet
	Land; hilly. Soil; 2nd rate.	
	N. on E. Bdy. of Sec. 13. Var. 20° 45' E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound of earth with charred stake, pits, trench, etc. as per instructions.	
64.70	Road brs. E. & W.	
80.00	Set stone, 15 x 7 x 7 ins. for Cor. to Secs. 12, 13, 7 & 18 Land; gently rolling. Soil; 2nd rate.	
	N. on E. Bdy. of Sec. 12. Var. 19° E.	
40.00	Set stone, 20 x 10 x 4 ins. for $\frac{1}{4}$ Sec. Cor.	
80.00	Set post for Cor. to Secs. 6, 7, 1 & 12, in mound of earth with charred stake, pits, trench, etc., as per instructions. Land; level. Soil; 1st rate.	
	N. on E. Bdy. of Sec. 1 Var. 21° E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound of earth, with charred stake, pits, trench, etc. as per instructions.	
80.81	Intersect Base Line and set post for Cor. to Tp. 1 S., Rs. 31 & 32 E., in mound of earth with charred stake, pits, trench, etc., as per instructions. Note: The intersection is 950 lks. W. of Tp. Cor. to Tp. 1 N., Rs. 31 & 32.	
	South Bdy. T. 1 S., R. 31 E., W.M. Same Deputy-Surveyor, under same Contract and date. Var. 20° 30' E.	
40.00	E. on N. Bdy. of Sec. 6. Set post for $\frac{1}{4}$ Sec. Cor. in mound of earth, with charred	