

T. 1 S., R. 31 E., W.M.

Chains		Feet
	Land; hilly. Soil; 2nd rate.	
	E. on a random line bet. Secs. 25 & 36.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.50	Intersect E. Bdy. at Cor. of Secs. 25 & 36, from which Cor. I run	
	W. on a true line bet. Secs. 25 & 36.	
33.68	Road brs. N.E. & S.W.	
40.25	Set post for $\frac{1}{4}$ Sec. Cor. in mound of earth with charred stake, pits, etc., as per instructions.	
47.00	Birch Creek, 6 lks. wide, runs N.E. Ascend hill.	
80.50	The Cor. to Secs. 35, 36, 25 & 26. Land; on E. $\frac{1}{2}$ mile gently rolling, West $\frac{1}{2}$ hilly rolling. Soil; first rate; W. $\frac{1}{2}$ -2nd rate.	4500
	N. bet. Secs. 25 & 26. Var. 19° 30' E.	
	Descend hill.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound of earth, with charred stake, pits, etc., as per instructions.	
80.00	Set post for Cor. to Secs. 23, 24, 25 & 26, in mound of earth, with charred stake, pits, etc., as per instruc- tions.	
	Land; hilly. Soil; 2nd rate.	
	E. on a random line bet. Secs. 24 & 25.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.75	Intersect E. Bdy. at Cor. to Secs. 24 & 25, from which I run	
	W. on a true line bet. Secs. 24 & 25.	
40.38	Set stone, 14 x 8 x 6 for $\frac{1}{4}$ Sec. Cor.	
80.75	The Cor. to Secs. 23, 24, 25, & 26. Land; level. Soil; 2nd rate.	