

T. 1 S., R. 31 E., W.M.

Chains		Feet
80.30	The Cor. to Secs. 11, 12, 13 & 14. Land; rolling. Soil; 1st rate.	
<hr/>		
N. bet. Secs. 11 & 12. <div style="text-align: right;">Var. 19½° E.</div>		
12.08	Road brs. E. & W.	
40.00	Set stone, 20 x 12 x 10 for ¼ Sec. Cor.	
80.00	Set post for Cor. to Secs. 1, 2, 11 & 12, in mound of earth with charred stake, pits, etc., as per instructions. Land; gently rolling. Soil; good 2nd rate.	
<hr/>		
E. on random line bet. Secs. 1 & 12.		
40.00	Set temp. ¼ Sec. Cor.	
80.18	Intersect E. Bdy. at Cor. to Secs. 1 & 12, from which, I run W. on a true line bet. Secs. 1 & 12.	
40.09	Set post for ¼ Sec. Cor., in mound of earth with charred stake, pits, etc., as per instructions.	
80.18	The Cor. to Secs. 1, 2, 11 & 12. Land; gently rolling. Soil; 2nd rate.	
<hr/>		
N. on a random line bet. Secs. 1 & 2. <div style="text-align: right;">Var. 20° E.</div>		
40.00	Set temp. ¼ Sec. Cor.	
80.70	Intersect N. Bdy., 30 lks. W. of Cor. to Secs. 1 & 2, from which, I run S.0° 13' W. on a true line bet. Secs. 1 & 2.	
40.70	Set stone, 15 x 12 x 10 for ¼ Sec. Cor.	
80.70	The Cor. to Secs. 1, 2, 11 & 12. Land; gently rolling. Soil; 1st rate.	
Nov. 12, 1864.		